

PEARL Reconditioning Standards			
LOW VOLTAGE TRANSFORMERS CONTROL POWER	Revision		
	Standard	Number	Date
	1420	5	11-2008

The term "reconditioning" is defined as "the process of returning electrical equipment to safe and reliable operating condition based on the design of the original manufacturer at the time of manufacturing."

NOTE: If fuses are installed, they are to be properly designed and rated with respect to voltage and interrupting rating for the device and specific application for which they are intended, and must be approved by the customer for said purpose. The final determination is ultimately the responsibility of the end user.

REFERENCES

The following references are use in this standard. Each of these references can be found in their respective listed locations.

Table References: Section 6000

Table 1: US Standard bus connection bolt torque values.

Table 6: Transformer Insulation Resistance Test Value

Table 11: Insulation resistance and test temperature conversion to 20°C values.

I TEST EQUIPMENT

The following test equipment is required to perform the testing requirements of this reconditioning standard:

1. Insulation Resistance Test Set (Megohmmeter) 1000 Vdc minimum

One of the following pieces of test equipment is required to perform the transformer ratio verification testing requirements of this reconditioning standard:

- 1 Turns-To-Turns Ratio Test Set
2. AC Voltage Supply and Voltmeter (+/- 0.5%)
3. Self-Contained Transformer Test Set

PEARL Reconditioning Standards			
LOW VOLTAGE TRANSFORMERS CONTROL POWER	Revision		
	Standard	Number	Date
	1420	5	11-2008

II RECONDITION EVALUATION

These steps are used to determine what will be required to recondition this product under this standard.

1 INSPECTION

1.1 Frame/Enclosure

- 1.1.1** Ensure that the nameplate data is legible.
- 1.1.2** Ensure that the third party listing service label is legible.
- 1.1.3** Inspect for signs of corrosion.
- 1.1.4** Inspect all connections for missing hardware.
- 1.1.5** Record results on an approved PEARL Evaluation Form.

1.2 Winding(s)

- 1.2.1** Inspect for cracked insulation.
- 1.2.2** Inspect for signs of overheating.
- 1.2.3** Record results on an approved PEARL Evaluation Form.

1.3 Core

- 1.3.1** Inspect for signs of corrosion.
- 1.3.2** Inspect for signs of overheating.
- 1.3.3** Record results on an approved PEARL Evaluation Form.

PEARL Reconditioning Standards			
LOW VOLTAGE TRANSFORMERS CONTROL POWER	Revision		
	Standard	Number	Date
	1420	5	11-2008

2 TESTING

2.1 Insulation Resistance

2.1.1 Primary to ground test

2.1.1.1 Perform an insulation resistance test at test voltage specified in Table 6 of Section 6000. The test duration shall be for 1 minute.

2.1.1.2 Correct for temperature, if necessary (Table 11).

2.1.1.3 Record results on an approved PEARL Evaluation Form

2.1.2 Secondary to ground test

2.1.2.1 Perform an insulation resistance test at test voltage specified in Table 6 of Section 6000. The test duration shall be for 1 minute.

2.1.2.2 Correct for temperature, if necessary (Table 11).

2.1.2.3 Record results on an approved PEARL Evaluation Form

2.1.3 Primary to secondary test

2.1.3.1 Perform an insulation resistance test at test voltage specified in Table 6 of Section 6000. The test duration shall be for 1 minute.

2.1.3.2 Correct for temperature, if necessary (Table 11).

2.1.3.3 Record results on an approved PEARL Evaluation Form

2.1.3.4 Compare test results to manufacturer's recommendations or Table 6 of Section 6000.

2.1.4 The test results must be within the guidelines recommended in order for the product to become a PEARL labeled product.

2.2 Transformer Turns Ratio Verification

2.2.1 Perform a 'turns ratio test' on each phase from primary to secondary.

2.2.2 Record results on an approved PEARL Evaluation Form.

2.2.3 Compare test results to manufacturer's recommendations or industrial standards.

2.2.4 The test results must be within the guidelines recommended in order for the product to become a PEARL labeled product.

PEARL Reconditioning Standards			
LOW VOLTAGE TRANSFORMERS CONTROL POWER	Revision		
	Standard	Number	Date
	1420	5	11-2008

III RECONDITIONING PROCEDURES

The following procedures are in a recommended order and are required to recondition this product. PEARL recognizes that, based on actual product design and as found condition, some of these procedures may not be applicable. The testing requirement must be completed before the product can be labeled as a PEARL reconditioned product.

2 RECONDITIONING

1.1 Disassemble to clean.

1.1.1 Clean all parts of contamination and corrosion.

1.1.2 Prepare the frame/enclosure to paint, as necessary.

1.1.3 Paint frame/enclosure.

1.2 Coils and Insulators

1.2.1. Clean coils.

1.2.2. Clean insulators.

1.3 Missing or Defective Components, Parts and Hardware

1.3.1 Replace or repair any missing or defective components, parts and hardware found during the inspection phase of this standard.

2.4 Torque

2.4.1 Check all screw and bolt connections for the proper torque per manufacturer's recommendations or Table 1 of Section 6000.

2.4.2 Record results on an approved PEARL Reconditioning Test Form.

2.5 Final Assembly

2.5.1 Ensure that frame is plumb and square.

2.5.2 Cover any unused openings.

2.5.3 Ensure that the nameplate/label data is complete, correct and legible.

PEARL Reconditioning Standards			
LOW VOLTAGE TRANSFORMERS CONTROL POWER	Revision		
	Standard	Number	Date
	1420	5	11-2008

2 TESTING

2.2 Insulation Resistance

2.2.1 Primary to ground test

2.2.1.1 Perform an insulation resistance test at test voltage specified in Table 6 of Section 6000. The test duration shall be for 1 minute.

2.2.1.2 Correct for temperature, if necessary (Table 11).

2.2.1.3 Record results on an approved PEARL Reconditioning Test Form.

2.2.2 Secondary to ground test

2.2.2.1 Perform an insulation resistance test at test voltage specified in Table 6 of Section 6000. The test duration shall be for 1 minute.

2.2.2.2 Correct for temperature, if necessary (Table 11).

2.2.2.3 Record results on an approved PEARL Reconditioning Test Form.

2.2.3 Primary to secondary test

2.2.3.1 Perform an insulation resistance test at test voltage specified in Table 6 of Section 6000. The test duration shall be for 1 minute.

2.2.3.2 Correct for temperature, if necessary (Table 11).

2.2.3.3 Record results on an approved PEARL Reconditioning Test Form.

2.2.4 Compare test results to manufacturer's recommendations or Table 6 of Section 6000.

2.2.5 The test results must be within the guidelines recommended in order for the product to become a PEARL labeled product.

2.3 Transformer Turns Ratio Verification

2.3.1 Perform a 'turns ratio test' on each phase from primary to secondary.

2.3.2 Record results on an approved PEARL Reconditioning Test Form.

2.3.3 Compare test results to manufacturer's recommendations or industrial standards.

2.3.4 The test results must be within the guidelines recommended in order for the product to become a PEARL labeled product.

IV PEARL CERTIFICATION

This product has now been reconditioned under the PEARL Reconditioning Standard. The blue PEARL Reconditioning Quality Seal may now be placed on the device.